EXTRA ITEM RATE LIST

Name of Work: Improvements and Asphalting to Roads at Doddabommasandra, Krishna Temple Surrounding areas in Ward No. 09 (Vidyaranyapura).

Name of Agency: Sri Nataraj. T, No. 02, 1st Main, Amarajyothi Layout, RT Nagar, Bangalore - 32.

Estimated Cost: Rs. 30,00,000.00

Approved Amount : Rs. 25,53,460.39

Work Order No. BBMP/EE/BTP/WO/118/2020-21 Dated: 25.09.2020.

Sl. No.	Item No.	Description of Work	Unit	Qty	Rate	Amount	Whether the items are alternative to items in tender schedule or whether being an additional item	Wheather the extra items s included in the sanctioned Estimate	How the expenditure due to the extra item is proposed to be met out	Whether the item isincluded in the S.R (Referabce if SR to be given . If not Data Should accompany the EIRL	Remarks
1	E1	Construction of granular sub-base Grading-V as sub-base and drainage layer by providing coarse graded crushed stone aggregates of granite / trap / basalt material, mixing in a mechanical mix plant at OMC Carriage of mixed material to work site spreading in uniform layers with motor grader on prepared surface and compacting with vibratory power roller to achieve the 98% proctor density, complete as per specifications. Clause 401 of MORTH V Revision **Page No. 153, Item No. 20.5, PWD SR 2018-19**	Cum	148.31	1902.24	282121.21	Additional Item	No	By over all savings in the work	2018-19 PWD SR Rates	
		Total				**282121.21**					

Percentage Excess $\frac{\text{282121.21}}{\text{Approved Tender Amount } \text{2553460.39}} \times 100 =$ 11.05%

Assistant Engineer
Ward No. 09

Assistant Executive Engineer
Vidyaranyapura Sub Division
BBMP, Bangalore - 92

Assistant Executive Engineer
Vidyaranyapura Sub Division
BBMP, Bangalore - 92

Executive Engineer
Byatarayanapura Division
BBMP, Bangalore - 92